

The geologically fragile nature of the region and its remote location has been challenging for the Konkan Railway Corporation Ltd (KRCL), which is at the helm of the project. The USBRL built 22 km of roads for construction of this bridge alone. The danger of landslides meant that the two ends of the gorge, where the arch foundations are placed, were stabilized using, among other means, rock bolts that are 11 m long and 32 mm in diameter.



A long viaduct leads up to the Kauri end of the bridge. The area near the viaduct also houses the staff settlement of the railway project.